

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work: Improvements to Roads and Drains at Nanjappa Layout in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	305.00	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work.	Cum	208.93	Rupees Two Hundred Eight and Ninety Two Paise Only
2	49.95	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	5726.51	Rupees Five Thousand Seven Hundred Twenty Six and Fifty One Paise Only
3	104.90	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work.	Cum	6917.23	Rupees Six Thousand Nine Hundred Seventeen and Twenty Three Paise Only
4	6.29	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery etc., complete as per specifications and directions of engineer in charge of the work.	Tonne	71310.20	Rupees Seventy One Thousand Three Hundred Ten and Nineteen Paise Only
5	799.20	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc., complete as per specifications and directions of engineer in charge of the work.	Sqm	344.74	Rupees Three Hundred Forty Four and Seventy Four Paise Only

No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	299.70	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick etc., complete as per specifications and directions of engineer in charge of the work.	Sqm	738.90	Rupees Seven Hundred Thirty Eight and Ninety Paise Only
7	1665.00	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc., complete as per specifications and directions of engineer in charge of the work.	m	41.18	Rupees Forty One and Eighteen Paise Only
8	299.70	Providing two line dressing to granite stone slab / granite stone masonry etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1069.53	Rupees One Thousand Sixty Nine and Fifty Two Paise Only
9	9.99	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	6401.88	Rupees Six Thousand Four Hundred One and Eighty Eight Paise Only

~~Signature of the Contractor~~

[Signature]
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
20/02

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

[Signature]